

SCHEDULE-A

**Name of Work: Facelifting the external wall surfaces and improvement works at the open
terrace at Hotel Tamilnadu, Madurai-II**

Sl. No	Quantity (in figures and words)	Description of work	TNDSS No. of NBC .No	Rate (Figures and in words) Rs. PS	Unit (figures and in words)	Amount Rs. Ps
1	13.00 M3 (Thirteen Cubic metre)	Dismantling the damaged sun shade fins and properly stacked etc., complete as directed.	18		1 M2 (One Sq.m)	
2	21.00 M2 (Twenty one Square metre)	Solid PVC door shutters using 19 G 19mm MS square tubes for styles and outer frames.15mm Ms square tubes for top, lock and bottom rails. The steel tubes shall be covered with 5mm thick solid PVC sheets. Shutters using 5mm thick solid PVC sheets for panelling shall rigidly fixed in position including necessary furniture and fittings. The over all size of styles shall be 50mm x 30mm. The over all size of top rall, Lock rall and bottom rall shall be 75mm x 30mm . The over all size of frames shall be 50mm x 45mm, with suitable rabate for housing the shutter.	SS		1 M2 (One Sq.m)	

3	1917.00 M2 (One thousand nine hundred seventeen Square metre)	Finishing the top of roof with one course of machine pressed tiles of 230x230x20mm of approved quality laid in Cement Mortar 1:3 (One cement and three sand) mixed with water proof compound 2% by weight of cement used and top pointed with same mortar etc. complete - 10m2.	44 I		1 M2 (One Sq.m)	
4	120.00 M2 (One hundred Twenty Square metre)	Plastering for RCC works with Cement Mortar 1:3 (One cement and three sand) 12mm thick including water proofing compound, curing including taking, finishing neatly complying with standard specification .	56 & 57		1 M2 (One Sq.m)	
5	5350.00 M2 (Five thousand three hundred Fifty Square metre)	Painting two coats with ready mixed plastic emulsion paint of approved quality and colour over full putty finished wall surfaces including cost and conveyance of all materials etc. complete.	66A		1 M2 (One Sq.m)	
6	1150.00 M2 (One thousand one hundred fifty Square metre)	Painting two coats with ready mixed synthetic enamel paint of approved quality and colour over old wood works including cleaning the surface etc. complete.	67A		1 M2 (One Sq.m)	

7	230.00 M2 (Two hundred thirty Square metre)	Painting two coats with ready mixed synthetic enamel paint of approved quality and colour over old iron grill works including cleaning the surface etc. complete.	16.00		1 M2 (One Sq.m)	
SCHEDULE-B						
8	116.00 m3 (One hundred sixteen Cubic metre)	Weathering course with concrete broken brick jelly concrete on 20mm gauge in pure slacked shell lime (No sand to be used) over roof slab be proportion of brick jelly to lime being 32 Cft.: 12.5 Cft. well beaten wooden beaters giving the required shape and thickness as directed by the Corporation Officers - 10m3.	27.00		1M3 (One Cubic metre)	
9	1412.00 M2 (One thousand four hundred twelve Square metre)	Dismantling the existing pressed tiles and weathering course and properly stocked at Ground level for further use etc. complete.	74		1m2 (One Sq.m)	
10	160.00 M3 (One hundred sixty Cubic metre)	Conveyance charges for debris through the velbide (top covered by plastic mat) from Hostel Tamil Nadu 1 to away from the city limit (i.e. 10km fromt origin) The rate including loading and unloading etc. complete.			1M3 (One Cubic metre)	

11		Renewing the damaged and broken AC rain water down fall pipe with New PVC rain water down fall pipe of 110mm dia (4kg / m ²) of approved quality including fixing in position to true alignment with special clamp, TW plugs and screws etc. complete				
	100.00RM (Hudred Running metre)	<u>A) 4" dia PVC Pipes</u>	SS		1 RM (One Runningmetre)	
	25.00RM (Twenty five Running metre)	<u>B) 3" dia PVC pipes</u>	SS		1 RM (One Running metre)	
12		Supply and fixing the PVC specials of various dia (4 Kg / M2) of approved made etc. complete as per standard specification				
	5 Nos (Five numbers)	4" dia PVC bend	SS		E (Each)	
	2 Nos (Two numbers)	3" dia PVC bend	SS		E (Each)	
	5 Nos (Five numbers)	4" dia PVC shoe	SS		E (Each)	
	2 Nos (Two numbers)	3" dia PVC shoe	SS		E (Each)	

13	113.00 M2 (One hundred thirteen Square metre)	Brick Partition wall in CM 1:3 (One of cement and three of sand) 11.40CM thickness using country bricks of size 9" x 4 3/8" 2 3/4" including curing extra complete.	31 C		1m2 (One Sq.m)	
14	113.00 M2 (One hundred thirteen Square metre)	Plastering in Cement Mortar 1:5, 12mm thick including tacking finishing neatly complying with standard specification.	56 & 57		1m2 (One Sq.m)	
15	11.00 M2 (Eleven Square metre)	Special plastering for RCC slabs and beams with Cement Mortar 1:3, 10mm thick fine river sand including tacking finishing neatly complying with standard as specification directed	56 & 57		1m2 (One Sq.m)	
16	124.00 M2 (One hundred twenty four Square metre)	Painting two coats with approval cement paint over one priming coat of cement paint over cement plastered wall surface and ceiling including clearing, preparing the surface and curing etc. complete .	66 A		1m2 (One Sq.m)	

Signature of the Contractor

PROJECT ENGINEER

