

SCHEDULE- A – CIVIL WORKS

NAME OF WORK: IMPROVEMENT TO THE EXISTING VERANDAS IN GROUND FLOOR & FIRST FLOOR AT HOTEL TAMILNADU, THANJAVUR.

Sl.No	Quantity (in figures and in words)	Description of work	TNDSS No. of NBC .No	Rate (figures and in words) Rs. Ps.	Unit (figures and in words) Rs. Ps	Amount Rs. Ps
1	400.00 M2 (Four hundred Square metre)	Dismantling the existing ceramic or Mosaic tiles floor, walls and ceiling and clearing away the materials etc., complete as per standard specification.	18		1M ² (One Sq.m)	
2	200.00 M ² (Two hundred Square metre)	Dismantling the cement plastering from walls and cleaning away from site etc., complete as per standard specification.	18		1M ² (One Sq.m)	

3	395.00 M ² (three hundred nine five Square metre)	Flooring with vitrified tiles of approved quality colour design and size of 60cm x 60cm lead in CM 1:3 (One cement and three sand 20mm thick) including pointing the joints with same colour cement to the full depth of tiles including cost and conveyance of all materials and labour charges etc., complete.	39A		1M ² (One Sq.m)	
4	200.00M ² (Two hundred Square metre)	Daddoing the side walls with vitrified wall tiles of approved quality colour, design and of size 60cm x 30cm in cement mortar 1:2 - 12mm thick and painting with white cement including finishing the joint and polishing the tiles surface glassy etc., complete.	39A		1M ² (One Sq.m)	
5	1800.00M ² (One thousand eight hundred Square metre)	Applying full putty using ready mixed wall putty of approved quality over the old painted wall surface and ceiling including scrapping, cleaning, applying, putty and bringing the surface to a smooth finish including cost of all.	66		1M ² (One Sq.m)	
6	1800.00M ² (One thousand eight hundred Square metre)	Painting two cost with Plastic Emulsion paint of a approved quality and colour including the existing walls ceiling surface etc., as per standard specification.	66		1M ² (One Sq.m)	

7	295M ² (Two hundred ninety five Square metre)	Painting One coat of the ready mixed Synthetic Enamel paint of approved quality and colour over the existing painted wood surface like doors, windows and ventilators including scrapping cleaning preparing the surface scaffolding charges etc., complete.	66, 66A		1M ² (One Sq.m)	
8	295.00M ² (Two hundred ninety five Square metre)	Providing GYP board false ceiling using G.I channels, ceiling angles and section 10mm thick GYP board etc., complete. The perimeter channel will be fixed all round the walls. The intermediate channel will be fixed at every 4" centre and will be suspended from the ceiling using ceiling angles. The ceiling any section will be fixed with intermediate channel using connecting chip at every 2'C/C to from the grid of size 4' x 2' and the bottom of the grid will be fixed with 10mm thick plain GYP board. The GYP board and the joints of the surface will be made even using paper top jointing compound etc complete. (including cutting for light point)	SS		1M ² (One Sq.m))	
9	320.00 M (Three hundred twenty metre)	Providing cornice 6"x6" with plaster of paris(ready made)and fixing and one coat of primer etc.,complete.	66		1M (One metre)	

10	6 loads (Six loads)	Clearing the debris dismantled from floor tiles with cement Mortar from Verandas removing by lorry and deposited with minimum lead for 4km including heir charges for lorry loading and unloading charges etc., complete.	18		1 Load (One load)	
----	------------------------	---	----	--	----------------------	--

Signature of the Contractor

Project Engineer

SHCEDUEL-B (ELECTRICAL WORKS)

Sl. No	Quantity (in figures and words)	Description of work	TNDSS No. of NBC.No	Rate (Figures and in words) Rs. Ps	Unit (Figures and in words) Rs. Ps	Amount Rs. Ps
11	36 Nos (Thirty six numbers)	Supply and fixing 15 Watts CFL, vertical lamp recess mounting integral Down Lighter with bright reflector inclusive of gearbox and with 13 watts CFL, bulb on false ceiling giving wire connection, testing, etc.,			1 No (One number)	
12	120.00 mtr (One hundred twenty metre)	Supply and run of 2 of 4 Sq.mm PVC insulated SC unsheathed Cu conductor 1100 V grade in PVC rigid pipe concealed in wall and ceiling with continuous earth wire connection of 14 SWG TC wire and making good of the concealed portion.			Mt (metre)	
13	12 Nos (Twelve numbers)	Supply and fixing of 6" Ahuja Speaker on Gypsum False ceiling giving Speaker wire connection etc.,			1 No (One number)	
14	180.00 Mtr (One hundred eighty metre)	Supply and Run of speaker wire of best quality in suitable PVC pipe from Amplifier connector to the speaker in false ceiling, testing, etc.,			1 Mtr (One Metre)	

15	1 No (One number)	Supply and fixing of 32 A TPN Metal clad switch on suitable angle iron frame work with MS cable entry boxes with PWD earthing.			1 No (One number)	
16	300 Mtr (Three hundred metre)	Supply and run of 2 of 1.5 Sq.mm (22/0.3) PVC insulated SC unsheathed Cu. Conductor of 1100 V Grade in rigid pipe concealed in wall and ceiling with continuous earth wire connection of 14SWG TC wire and making good of the concealed portion with suitable colour.			Mtr (Metre)	
17	36 Points (Thirty six Points)	Wiring with 2 x 1.5Sq.mm PVC insulated SC unsheathed Copper conductor of 1100 V grade in suitable PVC pipe concealed in wall and ceiling with PVC accessories with latest model MK module type plate switches for concealed light point/ fan point			Pt (Point)	
18	5 pt (five points)	Wiring with 2 x 1.5 Sq.mm PVC insulated SC unsheathed Copper conductor of 1100 V grade in suitable PVC pipe concealed in wall/ ceiling with PVC accessories with latest model 5 A 3 pin MK module type plate switches with earth connection for concealed 5 A PVC plug point.			1 No (One number)	
19	2 Nos (Two numbers)	Supply and fixing of 8 way single pole and neutral MCB sheet steel enclosure Distribution board 1 No 32 Amps D MCB incoming 6 Nos 6 Amps to 32 Amps SPMCB outgoing in flush wqith wall earth making good of the concealed portion with earth connection only. The MCB DB and MCB's should be with ISI mark (Like Standard make)			1 No (One number)	

20	4 Nos (Four numbers)	Supply fixing of 18" size post top comteen Saturn midi ID 5911 lite model gate light fitting with Acrylic (clear cover) Doom with 11w CFL bulb and giving wire connection. The charges is including cost of GI pipe fixing on pillar/ pipe, etc.			1 No (One number)	
----	-------------------------	--	--	--	----------------------	--

Signature of the Contractor

PROJECT ENGINEER