

SCHEDULE - A

Name of Work: Upgradation of Bar at Hotel Tamilnadu, Rameswaram (Civil)

SL NO.	QUANTITY IN FIGURES	DESCRIPTION	TNDSS NO.OF NBC NO.	RATE IN FIGURES AND IN WORDS	UNIT IN FIGURES AND IN	AMOUNT
1	2	3	4	5	6	7
1		Dismantling, clearing away and carefully stocking the materials useful for reuse etc., complete				
1a	10 m3 (Ten cubic metre)	Brick masonry in cement mortar walls			1 cu m (One cubic metre)	
1b	2 Nos (Two Numbers)	Dismantled the wash basin 550mm x 400mm with clamps etc., complete			1 No. (One number)	
1c	20 m3 (Twenty cubic metre)	Dismantled panelled window and ventilator from its position as direct including hold fasts etc., complete			1 cu m (One cubic metre)	
1d	6 m2 (Six square metre)	Dismantling existing Bar counter/Bar display counter			1 sq.m (One square metre)	
2	3 m3 (Three cubic metre)	Construction of Brick work in CM 1:5 by using II class ground moulded chamber burnt bricks of size 0.9" x 4 1/2" x 0.3", the rate is inclusive of cost and conveyance of all material etc., complete			1 cu m (One cubic metre)	
3	28 m2 (Twenty eight square metre)	Construction of Brick partition wall for toilet by using II class ground moulded chamber brunt bricks of size 9" x 4 1/2" x 3" in CM 1:3 (One cement three sand) etc., complete.			1 sq.m (One square metre)	

4	50 m2 (Fifty square metre)	Plastering with cement Mortar 1:5 (One cement and five sand) 12mm thick in room ceiling and other plastering etc., complete			1 sq.m (One square metre)	
5	2 m2 (Two square metre)	Supplying and fixing in position of Aluminium anodized natural colour matt finish louvered ventilator the outer frame will be of 62x38x2mm @ 1.17 kg/m and louvers with moving arrangements will be made out of channels of size 60mm x 30mm x 4mm @ 0.27 kg/m with necessary glass of louvers 4mm thick aluminium clips including all materials etc., complete			1 sq.m (One square metre)	
6	1 No. (One Number)	Supplying and fixing in position of colour glazed earthen ware European water closet with 10 lit Low level fiber flush tank of approved quality (Parry ware or equivalent) with 100mm P or S trap with double flapped colour seat cover with CP brass hinges, 40mm dia, flush bend, 15mm dia, Brass connection, 15mm dia Brass nipple, 15mm dia. CP angle valve fixing the cistem			1 No. (One number)	
7	1 No. (One Number)	Solid PVC door shutter using 19 gauge 19mm MS sq tubes for styles and outer frames. 15mm MS sq tubes for top lock and bottom rails. The steel tubes shall be covered with 5mm thick solid PVC sheets for paneling shall rigidly fixed in position including necessary brass furniture and fitting. The over all size of styles shall be 50mm x 30mm The over all size of top rail, lock rail and bottom rail shall be 75mm x 30mm. The over all size of frames shall be 50mm x 45mm with suitable rebate for housing the shutter.			1 No. (One number)	

8	1 No. (One Number)	Supply and fixing in position of best quality approved make colour glazed. Earth ware wash basin of size 550mm x 400mm x 2 Nos. granite top of size 1.80m x 0.60m over all size including RCC slab concrete MS angle bottle trap all fittings etc., complete			1 No. (One number)	
9	10 Rm (Ten Running metre)	Supply and laying jointing of 20mm dia C pvc PIPE for approved make and quality including fixing CPVC specials but excluding cost of specifications etc., complete			1 Rm (One Running metre)	
10	11 Rm (Eleven Running metre)	Supplying laying, jointing in position of best quality 110mm dia PVC waste pipe (6kg/cm) of approved make (Finolex) and providing leak proof joints including making connection to all Sanitary fittings, dismantling, masonry RCC works wherever necessary and making good of dismantled portion complying with standard specifications.			1 m (One metre)	
11	4 Nos (Four Numbers)	Supply and fixing 0'4" dia PVC Nahini trap size 110mmx75mm of approved quality etc., complete as directed by the corporation officers.			1 No. (One number)	
12	4 Nos. (Four Numbers)	Supply and fixing of 0'4" CP crating of approved quality etc., complete.			1 No. (One number)	
13	1 No. (One Number)	Supply and fixing of 1/2" CP Bib cock long body of Jaguar or Equivalent make of approved quality including fixing in position			1 No. (One number)	
14	1 No. (One Number)	Supply and fixing 60cm dia CP towel rod, rack of approved make Jaguar or Equivalent including fixing in position			1 No. (One number)	

15	1 No. (One Number)	Supply and fixing colour porcelain soap dish of size 200mmx100mm x 65mm recess type of good quality and make.			1 No. (One number)	
16	1 No. (One Number)	Supplying and fixing 5mm thick bath room mirror of size of 0.75x0.60 with Aluminium frame 12mm x 12mm "L" channel and 8mm water proof plywood arrangements etc., complete as directed by the corporation officers.			1 No. (One number)	
17		Supplying and fixing following sides of PVC and CPVC specials approved quality and make complete			1 No. (One number)	
		PVC specials				
	3 Nos (Three Numbers)	a) 110mm dia PVC door Tee			1 No. (One number)	
	2 Nos (Two Numbers)	b) 110mm dia PVC bend			1 No. (One number)	
	2 Nos (Two Numbers)	c) 110mm dia PVC door bend			1 No. (One number)	
	2 Nos (Two Numbers)	d) 110mm dia PVC Tee			1 No. (One number)	
		CPVC specials				
	20 Nos (Twenty Numbers)	a) 0.3/4" CPVC Elbow, Urinal, wash basin + EWC			1 No. (One number)	

	12 Nos. (Twelve numbers)	b) 0.3/4" x 1/2" Brass Elbow			1 No. (One number)	
	6 Nos (Six numbers)	c) 0.3/4" CPVC union			1 No. (One number)	
	6 Nos (Six numbers)	d) 0.3/4" CPVC Brass valve			1 No. (One number)	
18	3 Nos (Three Numbers)	Supply and fixing in position of 75mm dia PVC waste pipe (6kg/m ²) of approved make and providing leak proof joint including making			1 No. (One number)	
19	3 Nos (Three Numbers)	Supply and fixing in position Indian make white glazed earthen ware lipped mouth flat back urinal of best approved quality with GI pipe connection of suitable length, 32mm bell mouthed PVC connection, 15mm dia GM gate valve fixing the urinal to the wall in position with necessary TW plugs, clamps, shellac etc., including dismantling masonry if necessary and redoing the same to original condition fixing the 15mm dia GI pipe and whelm valve. Painting the pipe with two coats of approved paint over one coat of primer and checked with out any leakage complete complying with standard specification. (The urinal should be got approved by the Executive Engineer before use on work)			1 No. (One number)	

20	12 m2 (Twelve square metre)	Flooring with Non slippery ceramic tiles of approve quality, colour design and of size 30cm x 30xm laid in cement mortar 1:3 20mm thick including pointing the joints with same colour cement to the full depth of the tiles including cost and conveyance of all materials.			1 sq m (One square metre)	
21	40 m2 (Forty square metre)	Dadoing the side walls with glazed wall tiles of approved quality colour, design and of size 30cm x 20cm in cement mortar 1:2 - 10mm thick and pointing with white cement including finishing the joint and polishing the tiles surface glassy etc., complete.			1 sq m (One square metre)	
22	2 m2 (Two square metre)	Supply and fixing in position of granite slab of size 0.75m x 0.95m of 20mm to 25mm thick in between urinals as directed. The rates inclusive of cost and conveyance of all materials			1 sq m (One square metre)	
23	20 m2 (Twenty square metre)	Supply and fixing of RCC slab 0-2" thick (or) 50mm thick for the store room slab to store the cellar room.			1 sq m (One square metre)	
24	25 m2 (Twenty five square metre)	Painting two coats with ready mixed synthetic enamel paint of approved quality and colour make over the existing surfaces etc., complete			1 sq m (One square metre)	
25	30 m2 (Thirty square metre)	Painting two coats with ready mixed plastic emulsion paint of approved quality and colour over full putty finished surfaces including cost and conveyance of all materials etc., complete			1 sq m (One square metre)	

SCHEDULE - A -1

Name of Work: Upgradation of Bar at Hotel Tamilnadu, Rameswaram (Interior Decoration Works)

1	85 sq m (Eighty five square metre)	Supply, laying and fixing of wood grain design, matt finish tiles of size 300mm x 600mm 9mm using NITCO JAVA PINE or Equivalent walnut tile over cement mortar 1:3 (One cement and three sand) 20mm thick bed including pointing to full depth with cerafil and colouring pigments matching the tile colours complying with standard specification. The rate is inclusive of cost of materials polishing curing, labourers conveyance labour, loading, unloading and all taxes etc for finished works neatly without stain and true level to place etc,m cinokete The colour of tiles shall be got approved before actual use on works.			1 sq m (One square metre)	
2	40 Rm (Forty Running metre)	Supply, laying and fixing MDF planks for skirting to a height of 4" and required size, the edges shall be chambered to 6mm and fixed with wall by using jumper screws. The plank surface shall be given required coat of Duco paint finish with artistic nature. The design of the artistic nature with Duco paint finish shall be got approved before execution.			1 Rm (One Running metre)	

3	92 sq m (Ninety two square metre)	<p>False ceiling</p> <p>Manufacturing and fixing of 3"x2" galvanized iron channel grids for fixing the 10mm gypsum board false ceiling channels on the grids galvanized iron grills, The iron grill should be suspended from existing RCC ceiling to required drop. The entire grid work must be sturdy on fixing with high graded fastener so as to with stand shelf weight of frame and Gypsum board channels support from lighting cutout wherever necessary as per design to be approved before suspension of false ceiling. The entire outer finish of wall Gypsum grids must be finished with Gypsum putty for ceiling joints and Gypsum paper for outer two coats. The entire frame work partition and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive of cost of materials labour charges conveyance, loading and unloading, finishing and erection etc., complete</p>			1 sq m (One square metre)	
---	--------------------------------------	--	--	--	------------------------------	--

4	50 Rm (Fifty running metre)	Wood finish joists in False Ceiling Manufacturing providing and fixing of decorative gypsum board false ceiling over 12mm thick hard wood plywood box for girders and to soffits and ceiling. The finished Gypsum panels must be laminated with 1mm thick wooden lamination sheet and approved pattern with design. Entire girder work must be made with high grade hard wood plywood and fixed with high grade fastener so as to with stand its self weight and frame etc., for a size of 8' and 6' etc., The entire fabrication must be obtained appent by the departmental officers. The entire frame work portition and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive, loading and unloading, finishing and erection etc., complete			1 Rm (One Running metre)	
5	22 Rm (Twenty two Running metre)	Manufacutring supply and fixing decorative approved design 6" height POP cornice on wall surfaces whenever false ceiling works carried out to true alignment and level with splay of 45 degree at junctions complying with standard specification. The design and artistic type shall be got approved before execution.			1 Rm (One Running metre)	

6	6 sq m (Six square metre)	<p>Aluminium sliding window</p> <p>Supplying and fabrication and fixing in position of anodized natural colour matt finish sliding window in two track in all floors with following sizes 4'x4' all the shutters with sliding arrangements. The bottom section should have gutter arrangements so as to drain the water entering and made with extruded aluminium section for outer frames as shown below with necessary accessories such as rubber beading, Aluminium handle, stoppers and fixing 4mm thick frosted glass panels including all required for fabrication etc., complete including dismantling making holes in RCC columns, beams, masonry wherever necessary with power drill to the extent required and made it good to the original conditions after fixing as clips, rubber beading directed by the departmental officers. The entire frame work portition and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive of cost of materials labour charges conveyance, loading and un loadin, finishing and erection etc., complete.</p>			1 sq m (One square metre)	
---	------------------------------	---	--	--	------------------------------	--

7	6 sq m (Six square metre)	<p>Wooden Blains</p> <p>Manufacturing supplying and fixing wooden roller ups blend with 6" top over hand for windows with roller up, lock and release system as per design and patterns. The frame work and blains locking components must be of high grade, approved teak wood and teak leafs with French polish etc., complete apart from any shelf art design to be drawn as per departmental officers and standard specification etc., complete for size of 6' x 4'9", 4'x4'9" and 3'6" x 5'3". The entire frame work portition and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive, loading and unloading, finishing and erection etc., complete</p>			1 sq m (One square metre)	
8	9 Nos (Nine numbers)	<p>Fabricating, supply and providing M.S powder coated table of size 4' x2' with base frame height of 2'5" using M.S square pipes of 25x25mm and 12x12mm for base unit and 20mm thick finger joined compressed treated rubber wood sheet panel with chamfered. edge for sealing portion. The entire rubber wood seating position should be finished with MRC poly urethane glass coat /matt and tinted colour to walnut finish. The design of table and colour for base unit and top unit shall be got approved before fabrication asa per standard specification.</p>			1 No (One number)	

9	4 Nos (Four numbers)	Fabricating, supply and providing M.S powder coated table of size 2'3" x 2' with base frame height of 2'5" using M.S square pipes of 25x25mm and 12x12mm for base unit and 20mm thick finger joined compressed treated rubber wood sheet panel with chamfered. edge for sealing portion. The entire rubber wood seating position should be finished with MRC poly urethane glass coat /matt and tinted colour to walnut finish. The design of table and colour for base unit and top unit shall be got approved before fabrication asa per standard specification.			1 No (One number)	
10	44 Nos (Fourty four numbers)	CHAIRS: ARM CHAIR Manufacturing, supply and providing square or rectangle shaped and four legged arm chair using 20 gauge 25mm dia metre mild steel pipe with red oxide primer base and powder coating on the base to required micron. The seating and back rest should be made with treated cane splits woven and a coat of best French polish over the cane surface complying standard specification and as per the approved drawings and as directed. (Prior to manufacture the approved drawings may be obtained)			1 No (One number)	

11	5 Nos (Five numbers)	BAR STOOLS Manufacturing, supply and providing square or rectangular shaped and four legged Bar Stool using 20 gauge 25mm dia metre mild steel pipe with red oxide primer base and powder coating on the base to required micron. The seating and back rest should be made with treated cane splits woven and a coat of best French polish over the cane surface complying standard specification and as per the approved drawings and as directed. (Prior to manufacture the approved drawings may be obtained)			1 No (One number)	
12	7 sq m (Seven square metre)	BAR COUNTER Fabrication, supply and fixing of wooden Bar counter of size (15'-6" + 4'-6") x 3'-6" using 18mm and 12mm hard wood. The Skelton of Bar counter should be best approved CW scantlings, The Skelton or frame work should be made with provision with counter cabinet with shutters drawers with lock & key arrangements. Open storage and leg space for bar stool must be provided below the bar counter. All the surface area should be laminated with 1mm thick laminating sheets approved design and quality laminating sheets. The inside surface area must be finished with two coats of satin matt wood paint. The frame work of leg area in front, rear and sides must be laminated with 8mm thick MDF panel in relief with matching color duco paint finish. The rate is inclusive of cost of materials, labour conveyance fixing finishing etc., complete as per approved drawings (Prior to manufacture the approved drawings may be obtained)			1 sq m (One square metre)	

13	6 sq m (Six square metre)	<p>Counter Top</p> <p>Fabrication, supply and fixing wooden counter top of size (15'-6" +2'-6") + (4'-6"x2'-6") using best approved country wooden plank of uniform thickness of 20mm and the entire surface area should be laminated with 1mm thick approved design sheets and the edges alround of the wooden plank should be neatly laminated with 2mm thick PVC edge band with macro key design on top as per approved design drawings. The rate is inclusive of cost of materials, labour conveyance fixing finishing etc., complete as per approved drawings (Prior to manufacture the approved days may be obtained)</p>			1 No (One number)	
----	------------------------------	---	--	--	----------------------	--

14	15 sq m (Fifteen square metre)	<p>PARTITIONS Fabricating and providing wooden partition using 12mm thick hard wood outer panel and to inner rib support laminated with 1mm thick sheet as per design to a finished thickness of 3" as directed, complying standard specification, The partition must be embedded in to floor and wall without disturbing existing structure, floor and wall using rust proof fixtures and glue etc., complete The entire frame work and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive of cost of materials labour charges conveyance, loading and unloading, finishing and erection etc., complete. The following size of partitions.</p> <p>(3'6" x 3'6") x 5 (4'9" x 3'6") x 1 (2'0" x 3'6") x 2 (7'3" x 2'0") x 2 (6'10" x 2'0") x 2</p>			1 sq m (One square metre)	
----	-----------------------------------	---	--	--	------------------------------	--

15	4 sq m (Four square metre)	<p>PARTITIONS Fabricating and providing wooden partition using 12mm thick hard wood outer panel and to inner rib support laminated with 1mm thick sheet as per design and size of 3'6" x 7' 0" finished thickness of 4 1/2 " 6" as directed, complying standard specification, The partition must be embedded in to floor and wall without disturbing existing structure, floor and wall using rust proof fixtures and glue etc., complete The entire frame work and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive of cost of materials labour charges conveyance, loading and unloading, finishing and erection etc., complete.</p>			1 sq m (One square metre)	
16	5 sq m (Five square metre)	<p>Frosted glass in partitions Manufacturing supply and erection of 12mm thick frosted glass panel with 2 layers, frosting and etching as per the design evolved using stainless steel matt finish glass brackets fixed in position on partition wall to full depth for a size of (7'-3" x 1'-6") x 2 + (6'10" x 1'6") x 2 nos. frosted glass panel as directed complying standard specification. The entire frame work portion and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive of cost of materials labour charges conveyance, loading and unloading, finishing and erection etc., complete</p>			1 sq m (One square metre)	

17	1 Rm (One Running metre)	Fabricating supply and providing stainless steel hollow pipes with heavy guage with steel flanges, fixtures etc., for supporting pipes for Bar counters using S.S series jumber to fix the pipe with floor to bar count soffit. The entire design to leg may be got approved before fabrication.			1 Rm (One Running metre)	
18	5 sq m (Five square metre)	Bar counter shelves Manufacturing, fabricating, providing, supply and fixing of hard wood compressed plywood 12mm thick shelves. Both horizontal and vertical outer frame work and inner compartments, the entire surfaces must be finished with 1mm thick wooden lamination using bi-colours as per design for a size of (15'6" x 2'6") the door must be fixed with high graded brass inches and fixtures etc., The compartment must be fixed with brass angle and thread nuts as per standard specification.			1 sq m (One square metre)	

19	6 sq m (Six square metre)	Storage below Bar counter Manufacturing, fabricating, providing supplying and fixing of hard wood compressed plywood of thick 18mm for box work and teak wood clips for edges and shutters with 18mm thick hard wood compressed plywood for outer side with 1mm thick wooden finish lamination. The doors and shutters must be fixed with brass fasteners and auto closing hinges, the inner surfaces should be coated with one coat primer two coat of matt finish paint of approved quality colour as per standard specification. The size of shelves is 15'6" x 3'6". The entire frame work portition and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive, loading and unloading, finishing and erection etc., complete			1 sq m (One square metre)	
20	5 sq m (Five square metre)	Fabrication, Supply and providing Bar counters dummy base work for continuous display shelf made using 12mm thick hard wood plank. The surface of hard wood plank shall be laminated with wood finish lamination sheet of 1mm thick without air gap. The style and design of the wood finish lamination shall be got approved before actual use on works. The dummy base shall be of size 15'-6" x 2'-6"			1 sq m (One square metre)	

21	4 sq m (Four square metre)	Fabricating, supply and fixing hand wood wall panelling of 12mm thick, over the wall surfaces using jumper screw to horizontal and vertical plane without undulation over the hand wood surfaces 1mm thick wood finish lamination of approved design to be fixed with high bondage glue without air gap. The design shall be got approved before starting the work. The wall panel shall be of following size 4' -6" x 8'-0" -1 No.			1 sq m (One square metre)	
22	12 sq m (Twelve square metre)	Fabrication, supply and providing Niches on wall box work made using 12mm thick hard wood plank and fixed with jumper screw and levelling etc., complete. The surface of hard wood plank shall be painted with white duco paint. The dummy Niche shall be following sizes (6'-10" x 3'-6") + (11'-2" x 3'-6") + (6'-8" x 8'-2")			1 sq m (One square metre)	
23	50 sq m (Fifty square metre)	Wall Painting + Putty Painting the existing wall surfaces after through scrapping curing with water full putty with one coat of wall primer and two coats of acrylic emulsion paint complying standard specification and as directed. The rate is inclusive of cost of materials, labourers, transport landing and unloading, scaffloadings etc., complete. The colour and design of wall paintings should be got approved prior to paint the surfaces.			1 sq m (One square metre)	

24	85 sq m (Eighty five square metre)	Ceiling Painting + Putty Painting the existing wall ceiling surfaces after through scrapping, curing with water and full putty with one coat of wall primer and two coats of acrylic emulsion paint complying standard specification and as directed. The rate is inclusive of cost of materials, labourers, transport landing and unloading, scaffoldings etc., complete. The colour and design of wall paintings should be got approved prior to paint the surfaces.			1 sq m (One square metre)	
25	22 sq m (Twenty two square metre)	Supply and fixing vinyl fabric best approved design wall paper murals over the wall surfaces with out air gap and true alignment. The style or desing of wall paper shall be got approved before fixing. The wall paper to be pasted with high grade adhesive and should be water proof, peel proof and washable periodically by soft soap liquid as directed.			1 sq m (One square metre)	

26	5 sq m (Five square metre)	<p>Main Door</p> <p>Manufacturing, fabricating, providing and fixing of country wood door of size 3'3" x 7'0" - 2 nos. using best approved ompressed white country wood frame of size 4" x2'6" wooden plank with melamine polish and satin to walnut tinting and shutter with water proof compressed shutter of 30mm thick over which 1mm thick wooden lamination of approved design and pattern with SS matt finish with door handle and other fixtures with glass viewing panel of relieving design projection with 8mm thick compressed plywood and finished with approved wooden lamination as per standard specification. The entire frame work portition and its skelton must be prepared by the tender and should be got approved before fabrication. The rate is inclusive of cost of materials labour charges conveyance, loading and unloading, finishing and erection etc., complete</p>			1 sq m (One square metre)	
27	3 sq m (Three square metre)	<p>Fabricating supply and providing saloon type door of size 3'-0" x7'0" using compressed white wood frame of 4" x 2 1/2" with melamine polish and stained to walnut tinting. Shutter shall be with water proof compressed flushed doors of 30mm thick and should be laminated with patterned 1mm thick wood finish as per approved design. Necessary provision for Glass veiwing panel with S.S door fixtures and accesories shall also be made. The entire design of the door shall be got approved before fabrication and fixing in position.</p>			1 sq m (One square metre)	

28	1 No (One number)	Fabrication, supply and providing Architrave - trim 6" wide 18mm thick HDF plank 2'-0" dia ventilator. The HDF plank surfaces shall be given required coat of white Duco paint with artistic work. The entire design of ventilator and artistic work shall be got approved before fabrication and fixing.			1 sq m (One square metre)	
29	4 Nos (Four Numbers)	Fabricating, supply and fixing, modern CANVAS ART works using T.W frames of high quality and the T.W frames must be polished with sheenlac/French polish. The art work must depict tamil village folk dances/tourism theme/local tourist spots. The rate is inclusive of cost of materials, labourers, transport landing and unloading, scaffoldings etc., complete. The colour and design of wall paintings should be got approved prior to paint the surfaces. The art work scheme should be got approved before the canvas art work starts.			1 No (One number)	
30	5 Nos (Five numbers)	Manufacturing, supply and providing glass ware artefacts for decorative purposes in bar shelves. The nature of art work and theme to be depicted in the artefact works should be got approved before commencing the work.			1 No (One number)	
31	10 Nos (Ten numbers)	Manufacturing and providing "pottery bases" and "Tims" with modern aesthetic look for the NICHES as per approved design. The design shall be got approved before commencing the works.			1 No (One number)	

SCHEDULE - A -2

Name of Work: Upgradation of Bar at Hotel Tamilnadu, Rameswaram (Electrical Works)

1a	6 Nos (Six numbers)	Electrical Uplights in floor LED fitting fixed in floor with uplighting			1 No. (One number)	
b	6 Nos (Six numbers)	CFL 1x18w recessed light fitting in false ceiling			1 No. (One number)	
c)	4 Nos (Four Numbers)	Decorative light above bar counter			1 No. (One number)	
d	13 Nos (Thirteen Numbers)	Recessed LED spot light fittings in false ceiling			1 No. (One number)	
e	16 Nos (Sixteen Numbers)	LED lights in Bar counter and shelving behind			1 No. (One number)	

f	8 Nos (Eight Numbers)	5 Amps switch and sockets Using anchor or finolex cables with anchor modular switches			1 No. (One number)	
g	53 Nos (Fifty three numbers)	Wiring and switches			1 No. (One number)	
h	1 No. (One Number)	Distribution Board			1 No. (One number)	

**Dated, Signature of
The Tenderer / Contractor**

PROJECT ENGINEER